

616.23.3.28 (TA-28) Lane Closure on Alternate Passing Lanes

SPEED	SIGN SPACING (ft.)		TAPER LENGTH (ft.)		OPTIONAL	CHANNELIZER SPACING (ft.)	
	Undivided (S)	Divided (S)	Shoulder (1) (T1)	Lane (2) (T2)	BUFFER LENGTH (ft.) (B)	Tapers	Buffer/Work Areas
0-35	200	-	70	245	120	35	50
40-45	350	-	150	540	220	40	100
50-55	500	-	185	660	335	50	100
60-70	1000	-	235	840	550	60	100

1 Shoulder taper length based on 10 ft. (standard shoulder width) offset. 2 Lane taper length based on 12 ft. (standard lane width) offset.

TYPE OF ROADWAY	SIGN HEIGHT	MAXIMUM WORK ZONE LENGTH (L)
URBAN	1' Portable 7' Post	1 Mi.
RURAL UNDIVIDED	1' Portable 5' Post	3 Mi.

- Channelizer
- Sign
- Truck or Trailer Mounted Arrow Panel
- Protective Vehicle With Truck or Trailer Mounted Attenuator (TMA)
- Work Space

NOTES:

A protective vehicle **shall** be used while work is in progress. The protective vehicle **shall** be equipped with a TMA and flashing arrow panel and positioned at least 150 ft. in advance of the work space. The protective vehicle **may** be eliminated if the roadway is posted at 45 mph or below, the work vehicle is positioned in advance of the work space, and the work vehicle uses activated rotating lights or strobe lights.

For short duration operations, signs, and channelizers **may** be reduced or eliminated.

For mobile operations where workers are on foot and move with the operation, channelizers **may** be reduced or eliminated.

For one-lane mobile operations, refer to **616.23.3.4 (TA-4) Mobile Operation on Two-Lane Highways.**

For two-lane mobile operations, refer to **616.23.3.5 (TA-5) Mobile Operation on Divided or Multi-Lane Highways.**

Additional warning signs **shall** be erected at each intersection with another state highway within the work zone. Upon the discretion of the supervisor, additional warning signs **may** be erected at other intersections within the work zone.

